

DEPARTMENT OF LIVESTOCK PRODUCTION MANAGEMENT

S K N COLLEGE OF AGRICULTURE:JOBNER

No.SKN/RKVY-14/2020/172-176

Date:08.09.2020

Notice For Inviting Quotations

Sealed quotations are invited from the firms/manufacturers/suppliers/contractor for making enclosure with fencing work at RKVY-14, Department of LPM, SKNCOA, Jobner. The quotations will be accepted upto 10.09.2020 upto 11.00AM and will be opened on same day at 3.00PM in the department of Agronomy by the committee. The committee has all rights to accept/reject any quotation without assigning the reasons thereof.

SN	Name of work with Technical specifications
1	To prepare enclosure(145'x70') for Gir cows only on two sides with chain link fencing(4"gap with 12 gauge wire) work on iron angle 35x35x5mm with one door of 10'x5' of same material. Height of fence from surface will be 5'. All angle should be placed at 10' distance and 2' inside land with cement/concrete i.e. total length of angle would be 7'. The door should be well supported, matching with fence with proper locking facility. A barbed wire on top of the fence(approx 420') is to be done for strengthening fence. One coat of zinc oxide and black paint is essential on all iron angle.

Terms and condition:

1.The firm should submit their complete address/aadhar card/ GST registration with rates(FOR at Jobner) as per format given below.

SN	Name of work with technical specifications	Rate without GST in Rs	GST %	GST Amount in Rs	Total amount with GST in Rs
1	To prepare enclosure(145'x70') for Gir cows only on two sides with chain link fencing(4"gap with 12 gauge wire) work on iron angle 35x35x5mm with one door of 10'x5' of same material. Height of fence from surface will be 5'. All angle should be placed at 10' distance and 2' inside land with cement/concrete i.e. total length of angle would be 7'. The door should be well supported, matching with fence with proper locking facility. A barbed wire on top of the fence(approx 420') is to be done for strengthening fence. One coat of zinc oxide and black paint is essential on all iron angle.				

2. Responsibility of GST/taxes/charges/all required material/transport/labour/etc will be of firm.
3. It will be treated as a single work and rates are to be submitted treating as single work.
4. Firm will have to complete the work within a period of 07 days after receiving order.
5. Firms may visit site between 10.00AM to 5.00PM and complete work is to done at the site.

/
Head,LPM

Copy to:

1. The Dean,SKNCOA,Jobner
2. The Convenor, DDO and all members of tender committee
3. Dr Athar Uddin, Professor,LPM
4. Incharge, CIMCA, SKNAU, Jobner with request to upload on university website.
5. Notice board: SKNCOA/LPM, Jobner/Nagar Palika Jobner,Purana Bazar,Jobner

/
Head,LPM