



Dr. S.S. Yadav
Officer Incharge Farms

INSTRUCTIONAL FARM
S.K.N. College of Agriculture
Sri Karan Narendra Agriculture University : JOBNER – 303 329
E-mail : officerinc.farm@sknau.ac.in

No. Inst. Farms/Tender/SKNCOA/2023/141

Date: 05.06.2023

LIMITED TENDER NOTICE

Sealed tenders are invited from the reputed firms in prescribed format for the following works as per detail given below.

1.	Description of work	Supply of new geo membrane poly liner sheet (500 micron ISI marked) and related works of repairing the damaged farm pond (Karan Sagar), at keria Farm
2.	Approximate of cost (Rs.)	1.99 lakh
3.	Date of deposition of tender form	08.06.2023 11.00 AM
4.	Date of opening of tender	08.06.2023 12.30 PM

/
Officer Incharge Farms

Copy to:

1. Comptroller, S.K.N. Agriculture University, Jobner with request to appoint his nominee.
2. Dean, S.K.N. College of Agriculture, Jobner
3. The Convenor/member Tender committee, SKN CoA, Jobner
4. DDO, SKN CoA, Jobner
5. Incharge CIMCA with request to upload this tender on University website and SPPP portal.
6. Notice board, SKN CoA, Jobner
7. Tender file


05/06/23
Officer Incharge Farms

Format for Limited Tender

1. Name of Bidder :
2. Address :
-
3. Contact No.:
4. GST No. :
5. PAN No. :

S. No.	Name of item with specification	Approx. quantity required	Rates per unit offered with GST (Rs.)
1.	Removal of stone wall, stones and sand/mud from the damaged area of farm pond and proper shaping of the inlet point of water into the pond as well as its compaction to prevent erosion.	One unit	
2.	Digging of affected geo membrane liner sheet from trenches, cutting and removal of damaged liner sheet from the pond, checking leakages and their repairing, complete manual dressing and compaction of bottom, side walls and runoff water entry point of the farm pond in damaged area to make it suitable for installing geo membrane poly liner sheet of 500 micron.	One unit	
3.	Proper installation of geo membrane poly liner sheet (500 micron) in the affected and disturbed area of pond including all required manual and mechanical works viz., jointing of new sheet with old sheet, leveling, digging trenches and fixing the liner sheet ends into these trenches to protect from fast flowing runoff water etc.	One unit	
4.	Supply of new geo membrane poly liner sheet (500 micron ISI marked) to replace the damaged/ torn sheet of the farm pond.	1050.00 sq. meter	
	Note:- The facility of electricity/ generator for jointing of sheet will be provided by the college.		

Date :

Signature of Bidder



Terms and conditions:

1. The firm should have GST number and submit the GST certificate with tender.
2. The bidder should quote their rates in the prescribed format provided with tender.
3. The poly liner sheet (500 micron) should be ISI marked.
4. FOR at Instructional farm, SKNCoA (SKNAU), Jobner.
5. The successful bidder will have to complete the whole work within 10 days of placing work order.
6. Warranty for atleast 6 months for any leakage of water from joints.
7. Rate offered by the bidder will remain valid up to upper limit of the **tender value (Rs. 1.99 lakh) or for 3 months** period, whichever is earlier.
8. Payment will be made online after receiving satisfactory report.
9. The approximate purchasing can be **increased/decreased** as per requirement.
10. The committee has all right to accept/reject any tender without assigning the reasons thereof.

I have carefully read and studied all the terms and conditions and will comply these.

Date :

Signature of Bidder