

**DEPARTMENT OF LIVESTOCK PRODUCTION MANAGEMENT  
S K N COLLEGE OF AGRICULTURE:JOBNER**

No.LPM/2020/ 533-537

Date:07.10.2020

**Notice for Inviting Quotations**

Sealed quotations are invited from the firms/manufacturers/suppliers/contractor for providing and fitting two PVC tank assembly on Forage Farm at Department of LPM, SKNCOA, Jobner. The quotations will be accepted upto 13.10.2020 upto 11.30AM and will be opened on same day at 3.00PM in the department of Agronomy by the committee. The committee has all rights to accept/reject any quotation without assigning the reasons thereof.

SN	Technical specifications of PVC tank assembly	No.
1	Six Layer Polyethylene (PVC) Cylindrical Vertical Water Storage Tanks of 5000 Litres capacity with ISI mark. Preferably white colored. PVC tank should be having two vents with good quality valves of minimum 1.00 inch diameter. The PVC tank should be fitted on a durable concrete/masonry stand of minimum four feet height from ground. The tank should also be covered by suitable metal frame for avoiding theft and providing support to avoid being blown away by winds. This assembly should be complete in all terms including red oxide and suitable paint on metallic parts	02

**Terms and condition:**

1. The firm should submit their complete address/aadhar card/ GST registration with rates(FOR Dairy Farm at Jobner) as per format given below.

SN	Technical specifications PVC tank assembly	Rate/ PVC tank assembly without GST in Rs	GS T %	GST Amount in Rs	Total amount/ PVC tank assembly with GST in Rs
1	Six Layer Polyethylene (PVC) Cylindrical Vertical Water Storage Tanks of 5000 Litres capacity with ISI mark. Preferably white colored. PVC tank should be having two vents with good quality valves of minimum 1.00 inch diameter. The PVC tank should be fitted on a durable concrete/masonry stand of minimum four feet height from ground. The tank should also be covered by suitable metal frame for avoiding theft and providing support to avoid being blown away by winds. This assembly should be complete in all terms including red oxide and suitable paint on metallic parts				

2. Responsibility of GST/taxes/charges/transport/labour/etc will be of firm.
3. Rate should be given per PVC Tank assembly basis(PVC tank,stand,frame) including all charges.
4. Firm will have to complete the work within a period of 15 days after receiving order.
5. Quantity may increase or decrease.
6. Firm may visit site any time during office hours.

/

Head,LPM

Copy to:

1. The Dean,SKNCOA,Jobner
2. The Convenor, DDO and all members of tender committee
3. Dr Athar Uddin, Professor,LPM
4. Incharge, CIMCA, SKNAU, Jobner with request to upload on university website.
5. Notice board: SKNCOA/LPM, Jobner/Nagar Palika Jobner,Purana Bazar,Jobner

  
Head,LPM