



COLLEGE OF HORTICULTURE
(S.K.N. AGRICULTURE UNIVERSITY, JOBNER)
DURGAPURA, JAIPUR



Prof. L. N. Bairwa
DEAN & FC (Hort.)

Phone: 0141-2992057,(M): +91 9414932548
E-mail: dean.coh@sknau.ac.in

No.F()/SKNAU/COH/Store/NMPB Project/2026/ **380**


Date: **24/7/2026**

LIMITED TENDER NOTICE

Sealed Limited tenders are invited from the registered reputed, authorized manufacturers/firms/dealers /contractors for establishment of Nursery in infrastructure for QPM/Model Nursery of NMPB Project at COH, Durgapura Jaipur as mentioned in **Annexure-A**. Interested firms/tenderers may submit their rates/tender in enclosed format to this office latest by 12:00 Noon on 01.08.2026. The tender will be opened by the committee on the same day at 02.00 P.M. Approximate cost of items Rs. 1,25,000/-.

S. No.	Items/Works with Specifications	Quantity	Estimated cost including all taxes (Rs.)
1.	Establishment of Nursery :- 30 ft x 60 ft iron pipe Net House iron pipe structure and angle iron Jali frame with welded construction, concrete foundation and pipe column	As mentioned in Annexure- A	1,25,000/-

1. The tenders must be submitted in properly sealed envelope duly marked tender for the supply/establishing for.....
2. The rates quoted must be F.O.R. destination at COH, Durgapura, Jaipur
3. The undersigned is not bound to accept the lowest tender and reject any tender or any part of the tender without assigning any reason thereof.
4. The responsibility of GST/other charges, tax etc. applicable as per Govt. rules will be borne by the supplier.
5. GST/Registration and PAN are to be enclosed with tender.
6. Interested Tenderer may see the work site before submitting tender.
7. Work Area and items are estimated, payment will be made as per actual works and items on approved rate.
8. Rates will be include items, servicing and labour charges.


DEAN

Copy to followings for information and necessary action: -

1. The Incharge, SPPP/SHPP, COH, Durgapura to upload this Limited Tender on University Website/SPPP & SHPP Portals.
2. The Convenor, Tender Committee, COH, Durgapura, Jaipur.
3. The Members of Tender Committee, COH, Durgapura, Jaipur.
4. The DDO/Accts. Section, COH, Durgapura, Jaipur.
5. Tender File.
6. Notice Board, COH, and RARI, Durgapura, Jaipur.


DEAN

College of Horticulture, Durgapura

Size of Nursery for 30ft.x60ft - (Iron pipe Net House iron pipe structure and angle iron Jali frame with welded construction, concrete foundation and pipe columns)

Specification:-

S.No.	Size	Quantity
1.	Sand pipe (2"x2")	13ft x15Nos = 208ft
2.	Pipe outer frame (1"x2")	20ft x12Nos = 240ft
3.	Crossing pipe (1"x1")	20ft x15Nos = 300ft
4.	Poni inch Pipe	20ft x 5 Nos = 100ft
5.	Gate Frame Pipe (1.5"x1.5")	20ft x 3 Nos = 60 ft
6.	Iron Jali Frame (Width 1.5" and 2 mm thickness)	20 ft x 18 Nos = 360 ft
7.	Sporting patty 1" width and 2 mm thickness	20ft x 10 Nos = 200 ft
8.	Foundation Angle stand frame size 3" width and 2mm thickness	20 ft x 8 Nos = 160 ft
9.	Welding charge, cutting, joint, smooth, tapering	Pipe and Angle Joint welded.
10.	Foundation	15 columns with 2-3 ft deep PCC depth may increase based on soil condition.
11.	Sand	1 Brass sand
12.	Cement	10 Bags cement
13.	Manson charge	Manson for foundation work.
	Concrete Charge	PCC 1:3:6 for 15 columns
14.	Net Fitting Charge	Agri Net installation
15.	Net Purchase	1800 Sq ft.
16.	Iron Jali Fitting charge	Two side outer Frame fitting
17.	500 ltr water tank - 02 1000 ltr water tank - 02	Plastic, Channel, 50 meter pipe plastic - 1.5 inch and all necessary items
18.	Miscellaneous	

*Nursery structure with 7 ft. angle fencing around is covered with 70 mess green shade net and hand over after completion/working condition of nursery with one year guarantee.

Ban

College of Horticulture, Durgapura

Price format :-

S.No.	Size	Quantity	Quoted cost (Rs.)		
			Cost	GST	Total Cost
1.	Sand pipe (2"x2")	13ft x15Nos = 208ft			
2.	Pipe outer frame (1"x2")	20ft x12Nos = 240ft			
3.	Crossing pipe (1"x1")	20ft x15Nos = 300ft			
4.	Poni inch Pipe	20ft x 5 Nos = 100ft			
5.	Gate Frame Pipe (1.5"x1.5")	20ft x 3 Nos = 60 ft			
6.	Iron Jali Frame (Width 1.5" and 2 mm thickness)	20 ft x 18 Nos = 360 ft			
7.	Sporting patty 1" width and 2 mm thickness	20ft x 10 Nos = 200 ft			
8.	Foundation Angle stand frame size 3" width and 2mm thickness	20 ft x 8 Nos = 160 ft			
9.	Welding charge, cutting, joint, smooth, tapering	Pipe and Angle Joint welded.			
10.	Foundation	15 columns with 2-3 ft deep PCC depth may increase based on soil condition.			
11.	Sand	1 Brass sand			
12.	Cement	10 Bags cement			
13.	Manson charge	Manson for foundation work.			
	Concrete Charge	PCC 1:3:6 for 15 columns			
14.	Net Fitting Charge	Agri Net installation			
15.	Net Purchase	1800 Sq ft.			
16.	Iron Jali Fitting charge	Two side outer Frame fitting			
17.	500 ltr water tank - 02 1000 ltr water tank - 02	Plastic, Channel, 50 meter pipe plastic - 1.5 inch and all necessary items			
18.	Miscellaneous				

Signature and Seal of Firm Owner/Authorized person

