



OFFICE OF THE ESTATE OFFICER,
SRI KARAN NARENDRA AGRICULTURE UNIVERSITY,
JOBNER-303329 Distt. Jaipur (Raj.) Phone :-01425254982

No: F/ 13()/SKNAU/EO/Quotation/ 2026-27/1329-32

Date: 03.10.2026

Request for Quotation

Sealed Quotation are invited from the Registered Contractors to execution of the following works in the attached 'H' schedule. The quotation will be accepted up to **12.10.2026 at 12.00 P.M.** and will be opened on the same day at **12.15 P.M.** by the Estate Officer. Relevant registration certificate of contractor must be enclosed with 'G' schedule. The Estate Officer has all right to accept/ reject any quotation without assigning the reason. Quantity can be increase/ decrease.

Name of work:- Repair and Renovation of False Ceiling of University Main Gate, SKNAU, Jobner.

Estimated Cost: 55,000/-

Work Completion period : Fifteen Days.

ESTATE OFFICER

Copy to:-

1. The PS to the Vice Chancellor, SKNAU, Jobner.
2. The Comptroller, SKNAU, Jobner.
3. The Cashier/ Accounts, Estate Office, SKNAU, Jobner.
4. Notice Board- Office/
5. M/s.....
6. M/s.....
7. M/s.....

ESTATE OFFICER

OFFICE OF THE ESTATE OFFICER
SRI KARAN NARENDRA AGRICULTURE UNIVERSITY,
JOBNER-303329 Distt. Jaipur (Raj.)

Name of Work :- Repair and Renovation of False Ceiling of University Main Gate, SKNAU, Jobner.

Based on:- P.W.D. B.S.R. 2022.

"G" Schedule

BSR Item No	S.N o.	Particulars	Quantity	Unit	Rate	Amount	Total Amount in Words
10.35.4	1	Providing Solid PVC false Ceiling consisting of 600mm x 600mm, 5mm (±0.25) thick Plain embossed PVC sheet of Density 600 Kg /Cbm Manufactured by an ISO-9001-2015 certified Company, used as panel insert in a frame work made using powder coated aluminum T-section of sizes 1" x1"(25x25mm, 19 gauge or 1mm thick) in square pattern of grid sizes of 2"x2"(600x600mm). The aluminum framework is supported from the ceiling with the help of 'J' hook and G.I. wire / 6mm M.S. rods of required sizes to maintain proper level etc. The aluminum framework is supported on side wall with the use of aluminum L-section of size 1"x1" (25x25mm) angles etc. Complete as per direction of Engineer-In-charge, manufacturer's specification & drawing.	35.00	Sqm	1550.00	54250.00	Rupees Fifty Four Thousand Two Hundred Fifty Only
				Total amount		54250.00	Rupees Fifty Four Thousand Two Hundred Fifty Only



Estate Officer

I/we beg to tender as per% above/below of the "G" schedule

Signature of Contractor
 With full Address

Estate Officer